

BID SCHEDULE
WARRENTON MAIN AVENUE AT 9TH STREET SAFE ROUTES TO SCHOOL PROJECT

Bid Item No.	Description	Quantity	Unit	Unit Price	Bid Amount
1	MOBILIZATION (10%)	1	LS		
2	TEMPORARY WORK ZONE TRAFFIC CONTROL, COMPLETE	1	LS		
3	EROSION CONTROL	1	LS		
4	PLASTIC SHEETING	10	SQYD		
5	MATTING, TYPE B	20	SQYD		
6	INLET PROTECTION, TYPE 4	8	EACH		
7	SEDIMENT BARRIER, TYPE 3	300	FOOT		
8	POLLUTION CONTROL PLAN	1	LS		
9	CONSTRUCTION SURVEY WORK	1	LS		
10	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	1	LS		
11	CLEARING AND GRUBBING	0.13	ACRE		
12	GENERAL EXCAVATION	280	CUYD		
13	12 INCH DUCT IRON PIPE, 5 FT DEPTH	310	FOOT		
14	CONCRETE INLETS, TYPE G-2	1	EACH		
15	CONCRETE INLET, TYPE CG-48 (CWS)	3	EACH		
16	CONNECTION TO EXISTING STRUCTURES	1	EACH		
17	AGGREGATE BASE, 3/4"-0"	350	TON		
18	AGGREGATE BASE, 2-1/2"-0"	70	TON		
19	EMULSIFIED ASPHALT IN FOG COAT	6	TON		
20	LEVEL 3, 1/2 INCH ACP MIXTURE	80	TON		
21	CONCRETE CURBS	170	FOOT		
22	CONCRETE CURBS, CURB AND GUTTER	740	FOOT		
23	CONCRETE DRIVEWAYS	890	SQFT		
24	CONCRETE WALKS	2290	SQFT		
25	EXTRA FOR NEW CURB RAMPS	8	EACH		

26	TRUNCATED DOMES ON NEW SURFACES	100	SQFT		
27	CONCRETE CHANNEL INLET	2	EACH		
28	FIELD FACILITY MARKERS, TYPE S2	4	EACH		
29	PERMANENT SURFACE MOUNTED TUBULAR MARKERS	4	EACH		
30	LONGITUDINAL PAVEMENT MARKINGS - PAINT	400	FOOT		
31	THERMOPLASTIC, SPRAYED, SURFACE, NON-PROFILED	2000	FOOT		
32	PAVEMENT LEGEND, TYPE B-HS: BICYCLE LANE STENCIL	6	EACH		
33	PAVEMENT BAR, TYPE B-HS	325	SQFT		
34	PAVEMENT LEGEND, TYPE AB: ARROWS	7	EACH		
35	PAVEMENT LEGEND, TYPE AB: DISABLED PARKING	2	EACH		
36	REMOVE EXISTING SIGNS	1	LS		
37	PERFORATED STEEL SQUARE TUBE ANCHOR SIGN SUPPORTS	1	LS		
38	SIGNS, STANDARD SHEETING, SHEET ALUMINUM	50	SQFT		
39	FLASHING BEACON INSTALLATION, 9TH AND MAIN	1	LS		
40	WATER QUALITY FILTER STRIP, D01525	1	LS		
41	WATER QUALITY FILTER STRIP, D01526	1	LS		
42	PERMANENT SEEDING	1	LS		
43	MULTIPLE MAILBOX SUPPORTS	2	EACH		

TOTAL BID AMOUNT \$